EXTERIOR WALL ASSEMBLIES

WALL TYPE	DESCRIPTION
CW1	190 Aluminum Curtain Wall Thermally Broken Sealed Unit Glazing w/ 6mm Tempered Glass
CW2	190 Aluminum Curtain Wall Sealed Unit Glazing w/ 6mm Tempered Glass
W1	6 EIFS 100 Rigid Insulation Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Gypsum Board
W2	40 Prefinished Vertical Metal Cladding 25 Air Space 100 Rigid Insulation 125 Horizontal Z-Bars @ 600 O.C. Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Gypsum Board
W3	6 Acrylic Stucco W/Mesh Reinforced Base Coat 13 Cement Board 25 Air Space 100 Rigid Insulation 125 Z-Bars, Grid @ 600 O.C. Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Gypsum Board
W4	40 Aluminum Composite Panels 25 Air Space 100 Rigid Insulation 125 Z-Bars, Grid @ Perimeter Of Panels Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Gypsum Board 25 Air Space 100 Rigid Insulation 125 Z-Bars, Grid @ Perimeter Of Panels Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Gypsum Board
W5	100 Precast Concrete Panels 25 Air Space 100 Rigid Insulation Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Gypsum Board
W6	40 Aluminum Composite Panels 25 Air Space 100 Rigid Insulation 125 Z-Bars, Grid @ Perimeter Of Panels Vapour Barrier (Self-Adhered) 200 C.I.P. Concrete
W7	100 Precast Concrete Panels 25 Air Space 100 Rigid Insulation Vapour Barrier (Self-Adhered) 200 C.I.P. Concrete
W8	40 Aluminum Composite Panels 25 Air Space 100 Rigid Insulation 125 Z-Bars, Grid @ Perimeter Of Panels Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C.
W9	100 Rigid Insulation Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Gypsum Board

PARAPET ASSEMBLIES

WALL TYPE	DESCRIPTION
PT1	6 Acrylic Stucco 100 Rigid Insulation Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Pre-primed Plywood Membrane Counter-Flashing
PT2	40 Prefinished Vertical Metal Cladding 25 Air Space 100 Rigid Insulation 125 Horizontal Z-Bars @ 600 O.C. Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Pre-primed Plywood Membrane Counter-Flashing
PT3	6 Acrylic Stucco W/Mesh Reinforced Base Coat 13 Cement Board 25 Air Space 100 Rigid Insulation 125 Z-Bars, Grid @ 600 O.C. Vapour Barrier (Self-Adhered) 13 Plywood Sheathing 152 Steel Studs @ 406 O.C. 13 Pre-primed Plywood Membrane Counter-Flashing
PT4	40 Aluminum Composite Panels 25 Air Space 100 Rigid Insulation 125 Z-Bars, Grid @ Perimeter Of Panels Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Pre-primed Plywood Membrane Counter-Flashing
PT5	100 Precast Concrete Panels 25 Air Space 100 Rigid Insulation Vapour Barrier (Self-Adhered) 13 Gypsum Board Sheathing 152 Steel Studs @ 406 O.C. 13 Pre-primed Plywood Membrane Counter-Flashing
PT6	40 Aluminum Composite Panels 25 Air Space 100 Rigid Insulation 125 Z-Bars, Grid @ Perimeter Of Panels Vapour Barrier (Self-Adhered) 200 C.I.P. Concrete

FLOOR ASSEMBLIES

FLOOR TYPE	DESCRIPTION
F1	120 thick concrete slab R/W 152x152 MW 9.1/9.1 Welded Wire Mesh (WWM) 0.15 Poly Moisture Barrier 50 Rigid Insulation (1200 wide around perimeter only) 200 Compacted Granular Fill (bearing grade)
F2	100 Concrete slab R/W 152x152 MW 9.1/9.1 WWM 38 Metal Deck
F3	200 Compacted Granular Fill (bearing grade)

INTERIOR PARTITIONS

TYPE	DESCRIPTION	FIRE RATING	STC
P1	200 C.I.P. Concrete	2-h	-
P2	13 Gypsum Wall Board 92 Metal Steel @406 O.C. 13 Gypsum Wall Board	45 min	-
P3	13 Gypsum Wall Board 92 Metal Steel @406 O.C. 89 Thick Absorptive Material 13 Gypsum Wall Board 13 Gypsum Wall Board	1-h	50 Db
P4	200 Nominal Concrete Block Units	1.5-h	50 Db
P5	16 Gypsum Wall Board 16 Gypsum Wall Board 92 Metal Steel @406 O.C. 89 Thick Absorptive Material 16 Gypsum Wall Board 16 Gypsum Wall Board	2-h	55 Db
P6	13 Gypsum Wall Board 13 Gypsum Wall Board 102 Metal Steel @406 O.C. 25 Air Space 16 Gypsum Wall Board 16 Gypsum Wall Board	2-h	50 Db
P7	13 Gypsum Wall Board 13 Gypsum Wall Board 152 Metal Steel @406 O.C. 13 Gypsum Wall Board 13 Gypsum Wall Board	2-h	50 Db
P8	64 Metal Steel @406 O.C. 13 Gypsum Wall Board	45 min	-
P9	16 Gypsum Wall Board 16 Gypsum Wall Board 64 Metal Steel @406 O.C.	2-h	-

ROOM SCHEDULE

NUMBER	NAME	AREA
T.O. MAIN FLOOR		
101	LOBBY	26.40 m²
102	VEST.	8.80 m²
103	RECEPTION	14.88 m²
104	SECURITY OFFICE	20.61 m²
105	CLASSROOM	53.67 m²
106	CORRIDOR	43.00 m²
107	SOUTH STAIRS	24.00 m²
108	JANITOR	4.76 m²
109	MENS CHANGE ROOM	17.24 m²
110	MENS WASHROOM	33.28 m²
111	UNIV. WASH	5.44 m²
112	WOMENS WASHROOM	30.46 m²
113	WOMENS CHANGE ROOM	19.62 m²
114	NORTH STAIRS	31.25 m²
115	KITCHEN	75.00 m²
116	MECHANICAL ROOM	15.92 m²
117	STORAGE	18.82 m²
118	STORAGE	34.98 m²
119	VEHICLE BAY	214.05 m²
120	STAFF LOUNGE	72.64 m²
T.O. 2ND FLOOR		
201	LOBBY	26.92 m²
202	WORSTATIONS	193.79 m²
203	SOUTH STAIRS	24.00 m²
204	JANITOR	4.66 m²
205	MEETING ROOM	19.79 m²
206	DISPATCH OFFICE	12.21 m²
207	DISPATCH OFFICE	8.85 m²
208	DISPATCH OFFICE	12.15 m²
209	DISPATCH OFFICE	10.23 m²
210	NORTH STAIRS	29.91 m²
211	STAFF LOUNGE	110.04 m²
212	STORAGE	74.36 m²
213	UNIV. WASH	8.01 m²
214	UNIV. WASH	7.55 m²
215	UNIV. WASH	9.04 m²
216	UNIV. WASH	9.38 m²
T.O. 3RD FLOOR		
301	LOBBY	47.08 m²
302	UNIV. WASH	6.57 m²
303	UNIV. WASH	6.36 m²
304	MEETING ROOM	41.77 m²
305	DISPATCH OFFICE	14.64 m²
306	DISPATCH OFFICE	10.72 m²
307	DISPATCH OFFICE	12.58 m²
308	DISPATCH OFFICE	12.52 m²
309	SOUTH STAIRS	24.00 m²
310	JANITOR	4.66 m²
311	WORKSTATIONS	200.93 m²
312	NORTH STAIRS	28.10 m²
T.O. ROOF DECK		
401	SOUTH STAIRS	24.00 m²

ROOF ASSEMBLIES

ROOF TYPE	DESCRIPTION
R1	2 ply SBS Roofing System 25 Fibreboard 250 Rigid Insulation Vapour Barrier (self-adhered) 13 Gypsum Board Thermal Barrier 38 Steel Deck
R2	2-Ply SBS Modified Bitumen Membrane System 25 Fibreboard 250 Rigid Insulation Vapour Barrier (Self-Adhered) 200 C.I.P. Concrete
R3	2-Ply SBS Modified Bitumen Membrane System 25 Fibreboard (MDF Fiberboard) 200 Rigid Insulation Vapour Barrier (Self-Adhered) 13 Gypsum Board Thermal Barrier 38 Steel Roof Deck

SOFFIT ASSEMBLIES

SOFFIT TYPE	DESCRIPTION
S1	900 X 900 Aluminum Composite Panel 25 Air Space 100 Rigid Insulation 125 Z-Bars, Grid @ Perimeter of Panels Vapour Barrier, Self-Adhered 13 Gypsum Board Sheathing 22 Hat Section Furring @ 600 O.C., Paralell To OWSJs 38 Carrying Channels @ 600 O.C. Suspension Rods @ 1200 O.C

CEILING ASSEMBLIES

CODE	DESCRIPTION
ACT1	600 x 600 Acoustic Lay-In Tile On T-Bar Grid
ACT2	1200 x 600 Acoustic Lay-In Tile On T-Bar Grid
GB1	64 Steel Carrying Channel 22 Steel Hat Furring Channel 13 Gypsum Wall Board

GENERAL NOTES

1. DRAWINGS ARE NOT TO BE SCALED.

2. ALL DIMENSIONS AND INSTALLATIONS ARE TO BE VERIFIED ON SITE.

3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO READ THIS DRAWING IN CONJUNCTION WITH ALL OTHER DRAWINGS INCLUDING OTHER CONSULTANTS' DRAWINGS AND TO BRING ALL OMISSIONS, DISCREPANCIES, INCLUDING DIMENSIONS, TO THE ATTENTION OF THE ARCHITECT PRIOR TO THE COMMENCING OF ANY WORK.

4. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT WHEREVER A FIRE SEPARATION IS REQUIRED AS INDICATED BY THE CONSTRUCTION DRAWINGS, ALL COMPONENTS OF THE ASSEMBLY ARE TO BE APPROVED MATERIALS WITHIN THE INSTALLATION/FABRICATION PROCEDURES PER DIRECTIONS OF THE U.L.C. NUMBER AND/OR REQUIREMENTS OF THE NBC - AB 2019. ALL FIRE SEPARATIONS MUST BE CONTINUOUS WITHIN THEIR EXTENT, AND ALL JOINTS TO BE AIR TIGHT.

5. SEAL ALL ARCHITECTURAL, STRUCTURAL, MECHANICAL OR ELECTRICAL PENETRATIONS IN WALL AND/OR FLOOR ASSEMBLIES WITH AN APPROVED PRODUCT / SYSTEM TO MAINTAIN REQUIRED FIRE RATING AND ACOUSTICAL MINIMUMS.

6. ALL BULKHEAD WALLS TO BE P# UNLESS OTHERWISE NOTED.

7. ALL COLUMN FURRING TO BE P# UNLESS OTHERWISE NOTED.

8. DIMENSIONS INDICATED ON FLOOR PLANS ARE (WHERE APPLICABLE) UNLESS OTHERWISE NOTED:
 A) TO GRID LINE
 B) EXTERIOR FACE OF SHEATHING
 C) CENTERLINE OF INTERIOR PARTITIONS
 D) FACE OF CORE OF INTERIOR FURRING WALLS

SEE FLOOR PLANS FOR ADDITIONAL DIMENSIONS.

NAIT
SCHOOL OF CONSTRUCTION AND APPLIED BUILDING SCIENCE
ARCHITECTURAL TECHNOLOGY

No.	Description	Date

NAIT AMBULANCE HEADQUARTERS

CONSTRUCTION ASSEMBLIES & NOTES

Class Number	A03
Date	23/03/2026
Drawn by	CHIDERA UZO
Instructor	ANDRE LUCENA

A0.1

Scale 1 : 1